

15-163-~~01007~~-00-00
19150

CP-3

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1962
JUL 16 11 1962
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Morganstern - Specter
Complete Address: Box 661 Russell, Kansas.
Lease Name Veverka Well No. 2
Location NE SW SW Sec. 27 Twp. 8 Rge. (E) (W) 19
County Rooks Total Depth 3411
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Ralph Lynch
Address: Great Bend, Kansas License No. 457
Operation Completed: Hour 5PM Day 11 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 263' circulated with cement - 5 1/2" 3405' with 100 sax cement & squeezed in Dakota with cement.
Sand back to 3400', set 4 sax cement with dump bailer - pulled 503' 5 1/2" -
circulated hole with heavy gel mud through 5 1/2" (11 sax Gel), displaced 20
sax cement through 5 1/2" at 550', heavy mud to 180', displaced 20 sax cement
through 5 1/2" at 180', heavy mud to 35', set plug and filled to bottom
cellar with cement.

Mudding and cementing by Lynch Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/19/62
INV. NO. 5396-w

Signed: [Signature]
Well Plugging Supervisor