

15-163-03181-58-00

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: SE SE NE Sec. 28 Twp. 8 Rge. _____ (E) _____ (W) 19

Name of Field: _____ Total Depth: 3454

I have this date completed supervision of plugging of:

Lease Name: Verveka Well No. 7

Operator's Full Name: Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor Ralph Lynch Pipe Pulling

Address: Great Bend, Kans License No. 396

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated; _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 5 Month 11 Year 61

The above well was plugged as follows:

8 5/8" 250' circulated with cement - 5 1/2" 3449' with 125 sax cement.

Filled with sand to 3440', set 5 sax cement with dump bailer, pulled

2595' 5 1/2" to 550', circulated hole with heavy gel mud through 5 1/2" at 550',

displaced 20 sax cement through 5 1/2" at 550', heavy mud to 170', displaced 20

sax cement through 5 1/2" at 170', heavy mud to 35', set bridge and 10 sax cement

to bottom cellar.

Mudding and cementing by Lynch Company pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 11/28/61

INV. NO. 4058-W