

15-163-20592-00-00

R

Form CP-3

Rev. 6-1-68

KANSAS

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JAN 5 1976

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

CONSERVATION DIVISION
Wichita, Kansas

15/76

Operator's Full Name F & M Oil Co., Inc. & Associates Oil & Gas

Complete Address 505 Union Center, Wichita, Kansas

Lease Name Veverka Well No. 1

Location SE NW NW Sec. 28 Twp. 8 Rge. (E) (W) 19

County Rooks Total Depth 3485'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drilling

Address Great Bend, Kansas License No.

Operation Completed: Hour 1 P Day 28 Month 12 Year 1975

The above well was plugged as follows:

RTD 3485' 8 5/8 csg set 205' cwc 140 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 1-5-76

INV. NO. 2518-W