

15-163-00372-00-00

Form CP-3  
Rev. 6-26-62

*11/24*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT **RECEIVED**  
STATE CORPORATION COMMISSION

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

NOV 24 1964

CONSERVATION DIVISION  
Wichita, Kansas

*11/24/64*

Operator's Full Name Okmar Oil Co

Complete Address: 1130 Wichita Plaza Wichita, Kans

Lease Name Ondrasek Well No. 3

Location NE SE NE Sec. 31 Twp. 8 Rge. (E) (W) 19

County Rooks Total Depth 3506

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest C asing Pulling

Address: Great Bend, Kans License No. 399

Operation Completed: Hour 10:30AM Day 21 Month 11 Year 64

The Above well was plugged as follows:

~~8 5/8" 107' circulated with cement - 5 1/2" 3502' with 100 sax cement -  
squeezed at 1150' with 200 sax cement.  
PB to 3421' Perf at 3298'.~~

~~Filled with sand to 3280', set 4 sax cement with dump bailer, pulled 90b'  
5 1/2" to 550' circulated hole with heavy gel mud through 5 1/2" at 550' ( 25 sax  
gel) pulled pipe to 450' - pumped mud and hole pressured up - pulled  
pipe to 550' - pumped and hole pressured up - pulled pipe to 230' - pumped  
and hole pressured up - pulled pipe to 185' and hole circulated at 185'-  
displaced 40 sax cement through 5 1/2" at 185', heavy mud to 35', cement 35'  
to 0'~~

Mudding and cementing by Southwest Company Pump Truck.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 11/25/64  
INV. NO. 204-11

Signed: Eldon Petty  
Well Plugging Supervisor