

15 - 163 - 19157 - 00 - 00

CP-3

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Lease Name Veverka Well No. 10

Location SE SW NE Sec. 28 Twp. 8 Rge. (E) (W) 19

County Rooks Total Depth 3478

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Lynch

Address: Great Bend, Kansas License No. 457

Operation Completed: Hour 5PM Day 13 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 178' circulated with cement - 5 1/2" 3476' with 125 sax cement & squeezed in Dakota section.

Sand to 3460', set 4 sax cement with dump bailer - pulled 551' 5 1/2" to 545', circulated hole with heavy mud (14 sax Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180', displaced 20 sax cement through 5 1/2", heavy mud to 35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Lynch Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/17/62

INV. NO. 5375-W

CONSERVATION DIVISION
Wichita, Kansas

Signed: [Signature]

Well Plugging Supervisor