

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

Form CP-3  
Rev. 6-2-68

RECEIVED  
STATE CORPORATION COMMISSION

JUL 05 1977  
07-05-1977  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 163 - 20585 - 00 - 00 (of this well)

Operator's Full Name Kansas Petroleum, Inc.

Complete Address 200 East First, Suite 100, Wichita, Kansas 67202

Lease Name Wolfenden Well No. 1

Location SW NE SE Sec. 30 Twp. 8 Rge. (E) (W) 19

County Rooks Total Depth 3458'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 10:30 A Day 30 Month 6 Year 1977

The above well was plugged as follows:

Total Depth 3458' 8 5/8 csg set 216' cwc 165 sk.

5 1/2 csg set 3452' cw 125 sk cem.

Allied Cementing Co. mixed & pumped down 5 1/2 csg W/45 sk cem. Top of cem. 3185'

Cutoff & recovered 2644' of 5 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs

hulls, followed with 70 sk 50-50 poz 6% -displaced with 12 sk gel & water -

released plug & capped with 70 sk 50-50 poz 6% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Leo Masney  
Well Plugging Supervisor

DATE 7-5-77

INV. NO. 5495-W