

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

DEC 10 1962

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
12/10/62

Operator's Full Name Fender Pipe & Supply
Complete Address: Box 302 Russell, Kansas
Lease Name Wines Well No. 1
Location N/2 N/2 SW Sec. 32 Twp. 8 Rge. (E) (W) 19
County Rooks Total Depth 3515
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Barnes & Sojis Pipe Pulling
Address: Russell, Kans License No. 9
Operation Completed: Hour 2PM Day 6 Month 12 Year 62

The Above well was plugged as follows:

8 5/8" 196' circulated with cement - 5 1/2" 3509' with 100 sax cement.
Sand back to 3500', set 4 sax cement with dump bailer - pulled 2462' 5 1/2"
to 600', circulated hole with heavy mud (22 sax Gel), displaced 20 sax
cement through 5 1/2" at 600', heavy mud to 180', displaced 20 sax cement
through 5 1/2" at 180', heavy mud to 35', - cement 35' to 0'

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edson Peck
Well Plugging Supervisor

DATE 12/10/62
INV. NO. 6181-W