

15-103-03185-00-02

Form CP-3
Rev. 6-26-62

**KANSAS
STATE CORPORATION COMMISSION**

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1964

CONSERVATION DIVISION
Wichita, Kansas

1/20/64

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Okmar Oil Co

Complete Address: 1130 Wichita Plaza Wichita, Kans

Lease Name Ondrasek Well No. 4

Location SE NE ~~SE~~ Sec. 31 Twp. 8 Rge. (E) (W) 19

County Rooks Total Depth 3510

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Operation Completed: Hour 2PM Day 18 Month 1 Year 64

The Above well was plugged as follows:

8 5/8" 114' circulated with cement. 5 1/2" 3508' with 75 sax cement - squeezed in Dakota section.

Sand to 3490', set 4 sax cement with dump bailer - pulled 900' 5 1/2" to 600', circulated hole with heavy gel mud (15 sax Gel), displaced 20 sax cement through 5 1/2" at 600', heavy gel mud to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35' cement to bottom cellar.

Mudding and cementing by Southwest Company pump truck

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/21/64

INV. NO. 8484-W

Signed: Edou Letty
Well Plugging Supervisor