

15-163-20220-00 Form CP-3
KANSAS Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1969
CONSERVATION DIVISION
Wichita, Kansas

6/30/69

Operator's Full Name T. O. Miller
Complete Address 619 Brown Building, Wichita, Kansas.
Lease Name Grace Lowry Well No. 1
Location NW-SW-SW, Sec. 31 Twp. 8 Rge. (E) (W) 19
County Rooks Total Depth 3603'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Gabbert-Jones, Incorporated.
Address 830 Sutton Place, Wichita, Kansas. License No.
Operation Completed: Hour 1:30 AM Day 23 Month 6 Year 1969

The above well was plugged as follows:

200' - 8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 565'.

Circulated hole with heavy mud. Pulled DP to 750' and displaced 200 Sx. cement thru
DP from 750' to 425'. Pulled DP to 210' and displaced 20 Sx. cement thru DP.
Pulled DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:

M. J. Deakins
Well Plugging Supervisor

DATE 7-1-69

INV. NO. 3-W