

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 5/9/77-15-165-29,694 (of this well). <sup>-00-00</sup>

(This must be listed; if no API# was issued, please note drilling completion date.) <sup>6/21</sup>

WELL OWNER/OPERATOR Bowman Oil Company OPERATOR'S LICENSE NO. 6931  
ADDRESS Box 17 Codell, Ks 67630 PHONE # (913) 434-2304  
LEASE (FARM) Kellogg WELL NO. B-1 WELL LOCATION SW SW SW COUNTY Rooks  
SEC. 23 TWP. 8S RGE. 19W (E) or (W) TOTAL DEPTH 3440 PLUG BACK TO         

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO.           
SURFACE CASING SIZE 8 5/8 SET AT 259 CEMENTED WITH 160 SACKS  
CASING SIZE 5 1/2 SET AT 3439 CEMENTED WITH 200 SACKS  
PERFORATED AT 3358

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Perforate 3400, 1340', 750', then cement with  
450 sacks 60/100 poz, 8% jel, 1/4# flocele per sack, plus 8 sacks hulls.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11/28/90 10:30 AM

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE  
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Paul H. Bowman PHONE # (913) 434-2304 11-28-90  
ADDRESS Box 17 Cpde11, Ks 67630

PLUGGING CONTRACTOR Halliburton Services LICENSE NO.         

ADDRESS Hays, Ks 67601 PHONE # (913) 625-3431 <sup>1550</sup>

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: *Paul H. Bowman*  
(Operator or Agent)

DATE: 11/26/90

④

15-163-20694-00-00

DRILLERS' WELL LOG

DATE COMMENCED: May 1, 1977  
DATE COMPLETED: May 9, 1977

Southern States Oil Company  
KELLOGG B-1  
SW SW SW  
Sec 23-T8-R19W  
Rooks County, Kansas

ELEVATION: 1931 K.B.

0 - 259'	Clay and Shale
259 - 695'	Shale, Sand Streaks
695 - 1060'	Shale, Sand
1060 - 1332'	Red Bed
1332 - 1572'	Anhydrite
1572 - 1545'	Shale
1545 - 3068'	Shale and Lime
3068 - 3072'	Shale
3072 - 3090'	Lime and Shale
3090 - 3106'	Lime
3106 - 3358'	Lime and Shale
3358 - 3440'	Dolomite
3440'	RED

FORMATION TOPS

Anhydrite	1332
Heebner	3068
Toronto	3090
Lensing	3108
Arbuckle	3358
RTD	3440

SURFACE PIPE:  
Set used 8 5/8", 28# pipe  
at 259' w/160 sacks Common,  
2% Gel, 3% cc.

PRODUCTION PIPE:  
Ran new 5 1/2", 14# casing at  
3439' w/200 sacks Common,  
10% salt, .75% CRF2 and  
10 bbl salt flush ahead.  
*APPROX TO 30' FROM*

A F F I D A V I T

STATE OF KANSAS )  
COUNTY OF BARTON ) ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 10th day of May, 1977.

Alvin M. Hague  
Notary Public

My Commission Expires: April 11, 1978

MAY 18 1977

*De la Cruz  
copy*

State of Kansas



15-163-20694-00-00

Kansas Corporation Commission

MIKE HAYDEN GOVERNOR  
KEITH R. HENLEY CHAIRMAN  
RICH KOWALEWSKI COMMISSIONER  
JACK SHRIVER COMMISSIONER  
JUDITH MCCONNELL EXECUTIVE DIRECTOR  
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

November 28, 1990

Bowman Oil Company  
Box 17  
Codell, KS 67630

Kellogg #B-1  
SW SW SW 23-08-19W  
Rooks County, KS  
API No. 15-165-20,694

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b).** Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Handwritten signature of David P. Williams in cursive.

David P. Williams  
Production Supervisor

District: #4, 2301 E. 13th  
Hays, KS 67601  
(913) 628 - 1200