

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 37-21

LOCATION N 3 31 E S 12

SEC. 21 TWP. 8 RGE. 19^W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Verveka

Operator W. L. Menzel et al Address c/o Stearns Operating Co
Russell, Kans

Field _____ County Rooks

Total Depth 3444 Feet.

Plugging Contractor Barnes & Sons Pipe Pulling

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 248' circulated with cement - 5 1/2" at 3441' with
125 sax cement behind - Cement to 3388' - perforated at 3374'
Filled with sand to 3365', set 4 sax cement with dump bailer,
pulled 2720' 5 1/2", mud to 240', set rock and 20 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

Eldon Kelly
District Conservation Agent
Date 6-10-54

REIVED
STATE CORPORATION COMMISSION

JUN 11 1954

PLUGGING
FILE SEC 21 T 8 R NW
BOOK PAGE 37 LINE 21