

15-163-01401-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 80-27

LOCATION SW NE NW

SEC. 22 TWP. 8 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Peterson

Operator Northern Ordnance Address Great Bend, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3437 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 180' circulated with cement - 5 1/2" at 3428'

with 100 sax cement behind.

Filled with chat to 3420', set 3 sax cement with dump bailer

pulled 2688' 5 1/2", filled hole with mud to 165', pumped in

30 sax cement from 165' to 30', filled with mud to 20',

set 3 sax cement to bottom cellar.

STATE CORP. COM.

CONSERVATION DIVISION

John J. Kelly  
District Conservation Agent

Date 5-28-51

5/31/51

**PLUGGING**  
FILE SEC 22 8 R19W  
BOOK PAGE 80 LINE 27