

15-163-03174-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 143-18

LOCATION SW NW SW

SFC. 22 TWP. 8 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Green

Operator J. B. Hawley Jr Address Columbia Heights  
Minneapolis, Minn.

Field \_\_\_\_\_ County Rooks

Total Depth 3460 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 300' circulated with cement - 5 1/2" at 3456' with  
60 sax behind.

Run 5 sax cement in bottom with dump bailer, pulled 2370'  
5 1/2", filled hole with commercial mud to ~~225'~~ 225' set  
rock bridge and 15 sax cement, filled with mud to 30', set  
plug and filled hole with cement to bottom cellar.

Commercial mud and pumping by Sun Cementing Co.

4/21/50

*Edon Teety*  
District Conservation Agent

Date 4-19-50

**PLUGGING**  
FILE SEC 22 TWP. 8 RGE. 19  
BOOK PAGE 142 LINE 18