

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 18 1977 5/18/77

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - 163 - 20,695 0000 (of this well)

Operator's Full Name Southern States Oil Co.
Complete Address Box 1365, Great Bend, Kansas 67530
Lease Name Kellogg "A" Well No. 1
Location 250' W SE NE NE Sec. 22 Twp. 8 Rge. (E) (W) 19
County Rooks Total Depth 3405'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Duke Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 11 A Day 17 Month 5 Year 1977

The above well was plugged as follows:

RTD 3405' 8 5/8 csg set 257' cwc 150 sx. Flg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 500' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

NOICED

Signed: Lisa Massey
Well Plugging Supervisor

DATE 5-18-77
INV. NO. 5177-W