

## DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 116-43LOCATION NW NW NESEC. 21 TWP. 8 RGE. 19Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease SilversOperator Aylward Drg Co Address 813 1st Natl Bldg WichitaField \_\_\_\_\_ County RooksTotal Depth 3473 Feet.Plugging Contractor West Supply Co

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_  
(Describe briefly the manner in which the well was plugged)

8 5/8" at 1475' circulated with cement - 5 1/2" at 3466' with  
150 sax cement behind.

Filled with sand to 3450', set 4 sax cement with dump bailer,  
pulled 2550' 5 1/2" - filled with mud to 200', set rock and 15 sax  
cement - filled with mud to 35', set rock and 10 sax cement to  
bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

may 27, 1955  
CONSERVATION DIVISION  
Wichita, Kansas

Edna Lee  
District Conservation Agent

DATE 5-21-55

PLUGGING	
FILE	EC 21-8 R 19W
BOOK	PAGE 116 LINE 43