

13-163-19155-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 125-18

LOCATION NW SW SW

SEC. 26 TWP. 8 RGE. 19

Dry Hole X Abandoned Oil Well 4 Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease E. Veverka 'B'

Operator Shell Oil Co Address

Field County Rooks

Total Depth 5414 Feet.

(Describe briefly the manner in which the well was plugged)

15" at 105' circulated with cement, 8 5/8" at 1394' circulated with cement - 4 1/2" at 5408 with 125 sax behind.

Lane-wells plugs to 5250, perforations at 5100', chat to 5150', Halliburton plug and 5 sax cement, pulled 4 1/2", mudded hole to 250', set wood plug and 15 sax cement, mudded hole to 50', set wood plug and 10 sax cement.

PLUGGING
FILE SEC 26 T 8 R 19 W
PAGE 185 LINE 18

[Signature]
DEC 6 - 1949
District Conservation Agent
Date 12-5-49
12/6/49