

15-163-20316-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1970
CONSERVATION DIVISION
Wichita, Kansas

7/20/70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Landes Exploration

Complete Address 418 Union Center

Lease Name Veverka Well No. 1

Location NW SW NW Sec. 26 Twp. 8 Rge. (E) (W) 19

County Rooks Total Depth 3175'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling

Address Victoria, Ks. License No.

Operation Completed: Hour 12 M Day 17 Month 7 Year 1970

The above well was plugged as follows:

RTD 3175' 8 5/8 csg set at 197' cwc. Cmt. Mat. 50-50 poz W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 7/20/70
INV. NO. 2251-W