

KANSAS

12
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

9/11/72
RECEIVED
STATE CORPORATION COMMISSION
APR 11 1972
CONSERVATION DIVISION
Wichita, Kansas

15-163-20426-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Black Petroleum, Inc.

Complete Address 445 Olive W. Garvey Bldg., Wichita, Kansas

Lease Name Veverka Well No. 1

Location SE NW NE Sec. 26 Twp. 8 Rge. (E) (W) 19

County Rooks Total Depth 3450'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Shields Drlg (Rotary)

Address Russell, Kansas License No.

Operation Completed: Hour 3 P Day 9 Month 4 Year 1972

The above well was plugged as follows:

RTD 3450' 8 5/8 csg set at 248' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill ipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Leo J. Massey*
Well Plugging Supervisor

INVOICED

DATE 4/13/72

INV. NO. 5539-10