

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1977
11/10/77
CONSERVATION DIVISION
Wichita, Kansas
(this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20,748 0000

Operator's Full Name J. B. Collins
Complete Address 1007 Cody-Suite "A", Hays, Kansas
Lease Name Veverka Well No. 5
Location C N/2 S/2 NW/4 Sec. 26 Twp. 8 Rge. (E) (W) 19
County Rooks Total Depth 3450'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Dreiling Oil
Address Victoria, Kansas License No.
Operation Completed: Hour 10 A Day 8 Month 11 Year 1977

The above well was plugged as follows:

RTD 3450' 8 5/8 csg set 214' cwc 140 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red Massey
Well Plugging Supervisor

NO. 11-10-77
6180-w