

15-163-1943-00-00

01000-00-00

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
CONSERVATION COMMISSION

APR 2 1962  
APR 3 1962  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Rooks

Location: NE NW SW Sec. 27 Twp. 8 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 19

Name of Field: \_\_\_\_\_ Total Depth: 3420

I have this date completed supervision of plugging of:

Lease Name: Verveka Well No. 4

Operator's Full Name: Morganstern & Spöcter Inc

Complete Address: Box 661 Russell, Kansas

Plugging Contractor Lynch Pipe Pulling

Address: Great Bend, Kans License No. 457

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 11AM Day 31 Month 3 Year 62

The above well was plugged as follows:

8 5/8" 256' circulated with cement - 5 1/2" 3416' with 100 sax cement.

Filled with sand to 3400', set 4 sax cement with dump bailer - pulled

1680' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" ( total of

18 sax @el & 4 sax Hulls) displaced 20 sax cement through 5 1/2" at 550',

heavy mud to 160', displaced 20 sax cement through 5 1/2" - heavy mud to

35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Lynch Company pump truck.

Signed: Edon Petty  
Conservation Division Agent

Reviewed: Harold J. Hollis  
Field Supervisor

Remarks:

INVOICED

DATE 4/5/62

INV. NO. 4495-W