

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 30 1962  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Morganstern - Specter  
Complete Address: Box 2526 Wichita (8) Kans  
Lease Name Veverka Well No. 1  
Location CS 1/2 SW SW Sec. 27 Twp. 8 Rge. (E) (W) 19  
County Rooks Total Depth 3408  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated: \_\_\_\_\_  
Plugging Contractor: Ralph Lynch  
Address: Great Bend, Kans License No. 457  
Operation Completed: Hour 12:30 PM Day 28 Month 10 Year 62

The Above well was plugged as follows:

8 5/8" 230' circulated with cement - 5 1/2" 3404' with 100 sax cement squeezed in Dakota series twice - cement ?

Filled with sand to 3390', set 4 sax cement with dump bailer, pulled 535' 5 1/2" to 530', circulated hole with heavy gel mud through 5 1/2" at 530', displaced 20 sax cement through 5 1/2" at 530' - heavy mud to 180' - displaced 20 sax cement through 5 1/2" at 180' - heavy mud to 35' set bridge and filled to bottom cellar with cement.

Mudding and cementing by Lynch Company pump truck.

**INVOICED**

I hereby certify that the above well was plugged as herein stated.

DATE 10/31/62  
INV. NO. 5928-W

Signed: Edward Perry  
Well Plugging Supervisor