

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 30 1962  
OCT 30 1962

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Morganstern - Specter  
Complete Address: Box 2526 Russell, Kans  
Lease Name Veverka Well No. 11  
Location NW SW SW Sec. 27 Twp. 8 Rge. (E) (W) 19  
County Rooks Total Depth 3418  
Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Ralph Lynch  
Address: Great Bend, Kans License No. 457  
Operation Completed: Hour 10AM Day 26 Month 10 Year 62

The Above well was plugged as follows:

8 5/8" 162' circulated with cement - 5 1/2" 3417' with 100 sax cement.  
Filled with sand to 3400' - set 4 sax cement with dump bailer.

Pulled 2725' 5 1/2" to 550' - circulated hole with heavy gel mud through  
5 1/2" - displaced 20 sax cement through 5 1/2" - heavy mud to 180', displaced  
20 sax cement through 5 1/2" - heavy mud to 35' set bridge and 10 sax cement  
to bottom cellar.

**INVOICED**

I hereby certify that the above well was plugged as herein stated.

DATE 10/31/62  
INV. NO. 5929-W

Signed: Edon Perry  
Well Plugging Supervisor