

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW NE NW

SEC. 27 TWP. 8 RGE. 19W

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease \_\_\_\_\_ Stice \_\_\_\_\_

Operator Sidey Oil Co Address *Blay & Ivan Blay*  
Russell, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3430 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 127' circulated with cement - 5 1/2" at 3427' with  
100 sax cement behind. Cement and calseal to 3313' - top perforation  
at 3250'.

Filled with sand to 3240', set 4 sax cement with dump bailer,  
pulled 2900' 5 1/2", filled hole with mud to 127', set plug and 15 sax  
cement, filled with mud to 35', set plug, rock bridge and 10 sax  
cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 16 1951  
NOV 16 1951  
CONSERVATION DIVISION  
Wichita, Kansas

*Leon Teley*  
District Conservation Agent

Date 11-12-51

PLUGGING  
FILE SEC. 27 T. 8 R. 19W  
BOOK PAGE 124 LINE 37

*F*