

15-163-02371-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rooks County. Sec. 21 Twp. 8 Rge. 19 (#) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SE SE SW

Lease Owner. Anderson-Prichard Oil Corp.

Lease Name. Veverka "A" Well No. 1

Office Address. Rt. #1 West 10th. - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole

Date well completed. September 18 19. 48

Application for plugging filed. September 24 19. 48

Application for plugging approved. Verbal Sept. 18 19. 48

Plugging commenced. September 18 19. 48

Plugging completed. September 18 19. 48

Reason for abandonment of well or producing formation. Dry Hole

If a producing well is abandoned, date of last production. 19.

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. M. A. Rives

Producing formation. Depth to top. Bottom. Total Depth of Well. 3545 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	251'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

From 3545' TD to 248' Heavy Rotary Mud
 From 248' to 246' Wooden Plug
 From 246' to 208 1/2' 15 sax cement
 From 208 1/2' to 30' Heavy rotary mud
 From 30' to 28' Wooden Plug
 From 28' to 6' 10 sax cement
 From 6' to surface Cellar

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. W. J. Dearen
Address. Anderson-Prichard Oil Corp. Route #1 West 10th. - Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Gerald M. Dougherty (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald M. Dougherty

Rt. #1 West 10th. Great Bend, Kansas (Address)


SUBSCRIBED AND SWORN to before me this 24 day of September, 19. 48

My commission expires 6-13-51

Henry Peacock Notary Public. sep 25, 1948

22-287

7-47-10M



DRILLER'S LOG

Company: Anderson-Pritchard Oil Corp.
The Derby Oil Company
Glenn W. Peel

Sec. 21 Twp. 8S Rge. 19W
SE SE SW

Farm: Veverka "A" #1

County: Rooks
Kansas

Total Depth: 3545'
Comm: 9-2-48 Comp: 9-18-48
Contractor: Glenn Peel Drilling Co., Inc.

Elevation:
Production: Dry

Casing:
8 5/8" 251' cem.

Figures below indicate bottom of formations

Rock	0 -	50
Sand		70
Shale and Sand		250
Shale		260
Sand		274
Shale and Shells		580
Sand		640
Shale and Shells		1060
Sand		1150
Shale		1465
Anhydrite		1490
Shale and Shells		1900
Shale and Lime		2030
Lime and Shale		2265
Shale and Lime		2475
Lime and Shale		2620
Shale and Lime		2685
Lime and Shale		2725
Shale and Lime		2854
Lime and Shale		2945
Shale and Lime		2988
Lime and Shale		3050
Shale and Lime		3256
Lime and Shale		3276
Lime		3545
Total Depth		3545

Sep 25, 1948

This is to certify that the above information is, to the best of our knowledge, true and correct.

GLENN PEEL DRILLING CO., INC.

BY: *[Signature]*

SUBSCRIBED AND SWORN to before me this 21st day of September, 19 48

My commission expires June 4, 1951 *[Signature]*
Notary Public

