


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks

County. Sec. 21 Twp. 8S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines

Lease Owner Aylward Drilling Company

Lease Name Silvers Well No. 3

Office Address 813 First Nat'l Bank - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed January 27, 1952

Application for plugging filed May 4, 1955

Application for plugging approved May 5, 1955

Plugging commenced May 11, 1955

Plugging completed May 17, 1955

Reason for abandonment of well or producing formation Operation unprofitable

If a producing well is abandoned, date of last production April 29, 1955

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 3444 Bottom _____ Total Depth of Well 3452 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	163'	None
				5-1/2"	3446'	2912'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3452' to 3430' and ran 4 sacks of cement. Mudded the hole to 163', set a 10' rock bridge and ran 15 sacks of cement. Mudded the hole to top and ran 10 sacks of cement. Plugging completed.

Name of Plugging Contractor West Supply Co., Inc. (If additional description is necessary, use BACK of this sheet)
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Paul W. Hesse

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Paul W. Hesse

813 First Nat'l Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of May, 1955

My commission expires December 11, 1957

Duane Jessup
Notary Public.



May 30, 1955

SILVERS #3

Casing Records:

8-5/8" - 163'
 5-1/2" - 3445 1/2'

Company: Aylward Drilling Co. - Berby, et al
 Contractor: Aylward Drilling Company

Commenced: January 8, 1952
 Completed: January 26, 1952

Description:
 SW/4 NE/4 NE/4
 Sec. 21-88-19W
 Rocks Co., Kansas
 Elev: 2807 Gr.
 2910 D.F.
 2913 R.B.

	From	To	Remarks
Foot Rock & Shale	0	47	
Shale & Sand	47	125	
Shale	125	163	
Shale & Shell	163	550	Set 8-5/8" casing @ 163' and cemented with 110 sax.
Shale & Sand	550	883	
Shale & Shell	883	950	
Sand	950	1095	
Shale & Shells	1095	1444	
Anhydrite	1444	1480	
Shale & Shells	1480	1650	
Shale & Lime Shell	1650	1915	
Shale & Lime	1915	3015	
Lime	3015	3303	
Lime & Chert	3303	3337	
Lime	3337	3450 T.D.	Set 5-1/2" casing @ 3445-1/2' and cemented with 75 sax.

Acidized with 500 gal. acid, snabbed 15 barre ls fluid 300' off bottom in 1 hr., 50% water.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Al Skalsky
 Al Skalsky

Subscribed and sworn to before me this 29th day of January, 1952.

My commission expires
 July 16, 1952

Flora Cooper
 Notary Public

PLUGGING
 FILE NO. 21-8-19W
 BOOK PAGE 116 LINE 43

RECEIVED
 MAY 5 1955