

15-163-02536-00-00  
WELL PLUGGING RECORD

OR

**FORMATION PLUGGING RECORD**

**OR**

•			

Rooks	County.	Sec 22	Twp 8	Rge 19	(X)	(W)
Location as "NE¼NW¼SW¼" or footage from lines NW SE NW						
Lease Owner. Northern Pump Company						
Lease Name. Peterson "A" Well No. 3						
Office Address. 1910 Broadway, Great Bend, Kansas.						
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole						
Date well completed.	November 29					19 48
Application for plugging filed.	November 29					19 48
Application for plugging approved.	November 30					19 48
Plugging commenced.	December 4					19 48
Plugging completed.	December 18					19 48
Reason for abandonment of well or producing formation. Dry Hole						

If a producing well is abandoned, date of last production.....19.....  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?.....Yes.....

Name of Conservation Agent who supervised plugging of this well Eldon R. Petty  
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3476 Feet  
Show depth and thickness of all water, oil and gas formations.

### CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to .....feet for each plug set.

Set Lane Wells Plug @ 3208 with 10 sacks of cement on top. Filled hole with heavy Rotary Mud to 170'. Plug set with 15 sacks. Cement and filled hole with mud to 30' of top and placed 10 sacks cement to top of surface casing.

RECEIVED

DEC 27 1960

1000

\_\_\_\_\_

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Chas. J. Beu  
Address 1910 Broadway, Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.  
Chas. J. Beu

Chas. J. Beu (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

1910 Broadway, Great Bend, Kansas.  
(Address)

(Address

SUBSCRIBED AND SWORN to before me this 27 day of December, 1948

My commission expires.

March 10, 1952.

Notary Public

22-2625

**PLUGGING**

FILE SEC 22 T 8 R 19 W

BOOK PAGE 71 LINE 4

15-163-02586-00-00

W. L. Hartman, Contractor  
Box 54  
Wichita, Kansas

NORTHERN ORDINANCE INC.  
Peterson #3  
NW SE NW Sec. 22-8-19W  
Rooks County, Kansas.

EL. 1999' D.F.

TOTAL DEPTH: 3475'  
Commenced: 10-26-48  
Completed: 11-29-48  
Casing: 8-5/8" -- 174' -- with 100 sx. cement.

Figures indicate bottom of formation:

0	to	80	Yellow Clay
80		120	Sand
120		170	Shale blue
170		425	Shale and Shells
425		975	Shale and Sand
975		1125	D-Sand
1125		1183	Shale
1183		1400	Shale
1400		1435	Anhydrite
1435		1545	Shale and Shells
1545		1900	Shale and Shells
1900		2045	Shale
2045		2190	Shale
2190		2225	Lime
2225		2330	Lime and Shale
2330		2400	Lime and Shale
2400		2510	Shale
2510		2615	Lime and Shale
2615		2705	Lime and Shale
2705		2795	Shale
2795		2825	Lime and Shale
2825		2860	Shale
2860		2935	Shale
2935		2970	Lime and Shale
2970		3007	Lime
3007		3109	Shale and Lime
3109		3187	Lime and Shale
3187		3237	Lime
3237		3285	Lime
3285		3339	Lime
3339		3406	Lime
3406		3443	Lime
3443		3475	Lime
		3475	TOTAL DEPTH

**RECEIVED**

Conservation Div.

NOV 30 1948


CORPORATION

MISSION

KANSAS

TOPS:

Topeka	2960	-961
Heebner	3149	-1150
Lansing-K.C.	3192	-1193
Arbuckle	3441	-1442
Rotary T.D.	3444	-1445



*Chas. A. Ben*