


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-163-03174-0020
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks _____ County, Sec. 22 Twp. 8 Rge. 19 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C. SW. NW. SW.
Lease Owner John B. Hawley, Jr.
Lease Name Green Well No. 1
Office Address Columbia Hts. P.O., Minneapolis 21, Minn.
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed December 30 19. 48
Application for plugging filed March 16 19. 50
Application for plugging approved March 17 19. 50
Plugging commenced April 11 19. 50
Plugging completed April 18 19. 50
Reason for abandonment of well or producing formation Non Commercial

If a producing well is abandoned, date of last production January 21 19. 50
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon R. Petty
Producing formation Arbuckle Dolomite Depth to top 3454 Bottom 3460 Total Depth of Well 3460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|------|--------|--------|------------|
| Arbuckle | Oil | 3456 | 3460 | 8-5/8" | 300' | None |
| | | | | 5 1/2" | 3456' | 2400' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pulled out 2400' of 5 1/2" casing. Mudded with Commercial Mud. Pumped with Sun Cementers to 225'. Dumped 15 sacks of cement with dump bailer and mudded hole back to 30', dumped 10 sacks cement in top 8-5/8" surface.

4/24/50

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to John B. Hawley, Jr.
Address Columbia Hts. P. O., Minneapolis 21, Minn.

STATE OF Kansas, COUNTY OF Barton, ss.
L. F. Browning (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. F. Browning
Box 317, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of April, 19. 50

My commission expires July 29, 1951

Zita S. Bird Notary Public.

22-5138 9-48-10M
PLUGGING
FILE SEC-22T 8 R 19W
BOOK PAGE 143 LINE 18

Contractor
 H. & H. Drilling Co.
 P.O. Box 54
 Wichita, Kansas

Company
 NORTHERN ORDNANCE INC.

15-423-03174-0000

Green #1
 C SW NW SW Sec. 22-8-19W
 Rooks County, Kansas.

E.L. 2005' D.F.

TOTAL DEPTH: 3458'
 Commenced: 11-17-48
 Completed: 12-8-48
 Casing: 8-5/8" --- 165' --- 100 Sacks Cement.

Figures indicate bottom of formation:

| | | | |
|------|----|-------|--------------------|
| 0 | to | 20 | Clay |
| 20 | | 100 | Lime |
| 100 | | 165 | Blue Shale |
| 165 | | 490 | Shale and Shells |
| 490 | | 665 | Sand and Shale |
| 665 | | 920 | Shale and Shells |
| 920 | | 1130 | Sand |
| 1130 | | 1340 | Shale |
| 1340 | | 1420 | Shale |
| 1420 | | 1450 | Anhydrite |
| 1450 | | 1465 | Shale |
| 1465 | | 1610 | Shale |
| 1610 | | 1855 | Shale and Shells |
| 1855 | | 1994 | Shale |
| 1994 | | 2165 | Shale |
| 2165 | | 2325 | Lime and Shale |
| 2325 | | 2400 | Shale and Lime |
| 2400 | | 2535 | Lime and Shale |
| 2535 | | 2620 | Lime and Shale |
| 2620 | | 2705 | Lime and Shale |
| 2705 | | 2797 | Shale |
| 2797 | | 2870 | Lime and Shale |
| 2870 | | 2983 | Lime and Shale |
| 2983 | | 3085 | Lime |
| 3085 | | 3157 | Lime |
| 3157 | | 3206 | Lime |
| 3206 | | 3245 | Lime K.C. |
| 3245 | | 3249 | Lime |
| 3249 | | 3279 | Lime |
| 3279 | | 3347 | Lime |
| 3347 | | 3365 | Cherty Lime |
| 3365 | | 3395 | Lime |
| 3395 | | 3441 | Lime |
| 3441 | | 3458 | ROTARY TOTAL DEPTH |
| | | | TOPS: |
| | | 2970' | (- 965) |
| | | 3161' | (-1156) |
| | | 3199' | (-1194) |
| | | 3408' | (-1403) |
| | | 3456' | (-1451) |
| | | 3458' | (-1453) |

3/17/50

PLUGGING
 FILE SEC 27 T 8 R 19W
 BOOK PAGE 143 LINE 18