

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-1163-01400-00-00

API NUMBER None

LEASE NAME PETERSON

WELL NUMBER 1

3630 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 22 TWP. 8S RGE. 19 XX (E) or (W)

COUNTY Rooks

Date Well Completed 1-9-48

Plugging Commenced 11-20-86

Plugging Completed 11-26-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS' LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays, KS

Is ACO-1 filed? on old form not, is well log attached? ----

Producing Formation Arbuckle Depth to Top 3451 Bottom 3456 T.D. 3456

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3451	56	10-3/4	187	-0-
				7	3451	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
11-20-86 pumped down 10-3/4" W/2 SXS hulls & 125 SXS 65/35 cmt. Pumped down 7" w/10 SXS cmt., 2 SXS celloflakes & 3 SXS hulls. Followed by add'l 115 SXS cmt. 11-26-86 cmt. fell to 1354' from first job. Open end & fill casing to surface w/115 SXS cmt. Pump in back side. JOB COMPLETE
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P.O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 19th day of January, 1987

My Commission Expires: Sept 29, 1987

Doris J. Russell
 Notary Public

STATE CORPORATION COMMISSION
 Form CP-4
 Revised 08-84

CONSERVATION DIVISION
 Wichita, Kansas

WICHITA, KANSAS