

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-23,138 5800

LEASE NAME Green

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

330' Ft. from S Section Line

4290' Ft. from E Section Line

LEASE OPERATOR Viking Resources, Inc.

SEC. 22 TWP. 8S RGE. 19 (E) or (W)

ADDRESS 105 S. Broadway, Suite 1040, Wichita, KS 67202

COUNTY Rooks

PHONE# (316) 262-2502 OPERATORS LICENSE NO. 5011

Date Well Completed _____

Character of Well D&A

Plugging Commenced 1-23-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-23-91

The plugging proposal was approved on 1-23-91 (date)

by Gib Scheck (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top _____ Bottom _____ T.D. 3427'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	211'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Fill w/heavy mud; set 1st plug 3400'-3300' w/25 sx; 2nd plug 1400'-1300' w/25 sx; 3rd plug @ 775'-375' w/100 sx; 4th plug @ 235'-75' w/40 sx, 1 sx Flocel; 5th plug @ 40' w/wiper plug w/10 sx; Rathole 15 sx; 215 sx 60-40 pozmix 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Viking Resources, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 26th day of January, 1991



Angela Woodard
Notary Public

My Commission Expires: March 20, 1993