


15-163-00330-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 23 Twp. 8S Rge. (E) 19 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW/4 NW/4 SW/4
Lease Owner N.C.R.A. & Musgrove Pet. Corp.
Lease Name William Veverka Well No. 1
Office Address 407 K.F.H. Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 13 19 51
Application for plugging filed June 13 19 51
Application for plugging approved June 13 19 51
Plugging commenced June 13 19 51
Plugging completed June 13 19 51
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3458 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				<u>8-5/8"</u>	<u>207'</u>	<u>Cemented</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 180'.
Set first plug at 180', spotted with 20 sacks
of cement through drill pipe.
Set second plug at 30' and spotted with 10
sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Musgrove Petroleum Corporation
Address 407 K.F.H. Building
Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GORDON L. KOELLING (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
407 K.F.H. Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of June, 19 51.

My commission expires December 5, 1951

Notary Public
RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1951
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 23 T 8 R AW
PAGE 88 LINE 12

621-51

15-163-00330-00-00

CONTRACTOR'S WELL LOG

COMPANY: National Cooperative Refinery Association
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: William Veverka #1
 LOCATION: NW/4 NW/4 SW/4, Section 23-T8S-R19W
 Rooks County, Kansas
 COMMENCED: May 27, 1951
 COMPLETED: June 13, 1951

0	5	Cellar
5	65	Soap stone and clay
65	585	Shale and shells
585	615	Sand
615	700	Shale and sand
700	835	Shale and shells
835	1045	Sand
1045	1145	Sandy red rock
1145	1250	Sandy shale
1250	1355	Red bed
1355	1400	Anhydrite
1400	1430	Shale
1430	1500	Shale and shells
1500	1580	Lime and shale
1580	1780	Shale and lime shells
1780	2125	Shale and lime
2125	2140	Pyrite
2140	2175	Shale and shells
2175	2200	Shale and lime shells
2200	2520	Shale and shells
2520	2565	Shale
2565	2700	Shale and shells
2700	2835	Shale and lime
2835	3005	Lime and shale
3005	3320	Lime
3320	3360	Lime and shale
3360	3397	Conglomerate
3397	3435	Lime and shale (cherty)
3435	3458	Arbuckle
	3458	Rotary Total Depth

Set 207' of 8-5/8" surface casing, cemented with 165 sacks.


Dry and Abandoned.

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of William Veverka #1, Sec. 23-8S-19W, Rooks County, Kansas, as reflected by files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
 Secretary



Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 18th day of June, 1951.

RECEIVED
 Notary Public
 JUN 21 1951

My commission expires: 12/5/51

CONSERVATION DIVISION
 Wichita, Kansas

621-51