


15-163 00406-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 23 Twp. 8 Rge. 19 (W) _____
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE SE
Lease Owner National Cooperative Refinery Association
Lease Name Peterson Well No. 1
Office Address 820 Union National Bank Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 27, 19 51
Application for plugging filed June 27, 19 51
Application for plugging approved June 28, 19 51
Plugging commenced June 28, 19 51
Plugging completed June 28, 19 51
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	198'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 190'. Set 1st Plug, spotted 20 sacks cement. Filled hole with heavy mud to 20: Set 2nd plug, dumped 10 sacks cement on up to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to National Cooperative Refinery Association
Address 820 Union National Bank Building
Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. Jean La Coss (employee of owner) or (~~owner or operator~~) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. Jean La Coss
820 Union National Bank Building
(Address)

SUBSCRIBED AND SWORN TO before me this 2 day of July, 19 51

My commission expires February 20, 1953.

28-5091-s 8-50-10M

RECEIVED Notary Public.
I. George
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 23 T 8 R 19W
BOOK PAGE 91 LINE 5

JUL - 3 1951
CONSERVATION DIVISION
Wichita, Kansas

17-3-51

CONTRACTOR'S WELL LOG

COMPANY: National Cooperative Refinery Association
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Petersen #1
 LOCATION: SW/4 SE/4 SW/4, Section 23-T28-R19W,
 Rocks County, Kansas
 COMMENCED: June 15, 1951
 COMPLETED: June 26, 1951

0	5	Cellar
5	40	Clay and rock
40	190	Clay, rock and shale
190	200	Shale and shells
200	450	Blue shale
450	1070	Shale, shells and pyrite
1070	1160	Sand
1160	1250	Shale and shells
1250	1290	Sand
1290	1330	Shale
1330	1365	Sand
1365	1405	Shale and sand streaks
1405	1420	Red bed
1420	1455	Anhydrite
1455	1475	Shale
1475	1875	Shale and shells
1875	1975	Shale and lime streaks
1975	3190	Shale and lime
3190	3400	Lime
3400	3460	Lime and shale
3460	3480	Lime
	3480	Rotary Total Depth

Set 198' of 8-5/8" surface casing, cemented with 170 sacks.

Dry and Abandoned.

STATE OF KANSAS }
) SS.
 COUNTY OF SEDGWICK }

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Petersen #1, Sec. 23-T28-R19W, Rocks County, Kansas, as reflected by files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
 Secretary

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 5th day of July, 1951.

Nadine L. Lively
 Notary Public

My commission expires: 12/5/51

9-13-51

PLUGGING
 FILE NO. 23-T-8-R19W
 BOOK PAGE 91 PAGE 5

RECEIVED
 STATE COMMISSION
 SEP 13 1951
 CONSERVATION DIVISION
 Wichita, Kansas