

15-163-21283-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
Form CP-4
Rev. 12-15-80
APR 16 1982

CONSERVATION DIVISION
Wichita, Kansas

4-16-82

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY _____ Rooks SEC. 23 TWP. 8S RGE. 19W E/W
Location as in quarters or footage from lines:

SE SW SW

Locate Well
correctly on above
Section Platt.

Lease Owner Bowman Oil Company

Lease Name Kellogg #3 Well No. _____

Office Address P.O. Box 17 Codell, Kansas 67630

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 4-8-82

Plugging completed 4-12-82

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hammel

Producing formation _____ Depth to top _____ bottom T.D. 3420'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	300'	none
				4-1/2"	3420'	437'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3700' and ran 4 sacks cement. Shot casing @2621', pulled on pipe and pipe parted, pulled a total of 11 joints of 4-1/2" casing.

Plugged well with 3 sacks hulls, 10 sacks gel, 1 sack hulls, 70 sacks cement, 5 sacks gel, 8-5/8" plug, 70 sacks cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April, 19 82

My Commission expires:



Irene Hoover
Notary Public.