


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County, Sec. 24 Twp. 8S Rge. _____ (E) 19 (W)
Location as "NE/CNW/SW" or footage from lines SE SW SW
Lease Owner Abercrombie Drilling, Inc.
Lease Name HANCE Well No. 1
Office Address 801 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 12, 19 64
Application for plugging filed December 12, 19 64
Application for plugging approved December 12, 19 64
Plugging commenced December 12, 19 64
Plugging completed December 13, 19 64
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Verbally - Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3575 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7 5/8	207	MP None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st Plug at 540' w/15 sx cement through DP
Set 2nd Plug at 200' w/15 sx cement through DP
Set 3rd Plug at 40' w/10 sx

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202

12-16-64

STATE OF Kansas, COUNTY OF Sedgwick, ss.
B. Lynn Herrington (employee of owner) ~~owner~~

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B. Lynn Herrington

801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 19 64

My commission expires June 16, 1967

Leah Faye Hefke
Leah Faye Hefke
Notary Public.

15-163-19143-00-00

CONTRACTOR'S WELL LOG

COMPANY:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
FARM:	HANCE #1
LOCATION:	SE SW SW Sec. 24-8S-19W Rooks County, Kansas
COMMENCED:	December 3, 1964
COMPLETED:	December 13, 1964

0	550	Shale
550	819	Sand and Shale
819	900	Shale
900	1100	Anhydrite and Shale
1100	1346	Shale
1346	1483	Red Bed
1483	1518	Anhydrite
1518	1735	Shale and Shells
1735	2035	Shale and Lime
2035	2177	Shale and Lime Str.
2177	3112	Shale and Lime
3112	3263	Lime
3263	3318	Lime and Chert
3318	3425	Lime
3425	3495	Lime and Cong.
3495	3575	Cong. Chert

Set 7 5/8" Surface Casing at 207' with 120 sacks Sunset Cement

DRY & ABANDONED

ELECTRIC LOG TOPS:

Topeka	2296'	(-947)
Heebner	3208'	(-1159)
Toronto	3229'	(-1180)
Lansing	3247'	(-1198)
Conglomerate	3483'	(-1434)
Log T. D.	3575'	(-1526)

ELEVATION: 2049' D.F.
& K.B.

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1964

12-16-64

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

CONSERVATION DIVISION
Wichita, Kansas

I, B. Lynn Herrington, do hereby certify that the above and foregoing is a true and correct copy of the log of the HANCE #1, SE SW SW Sec. 24-8S-19W, Rooks County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

B. Lynn Herrington
B. Lynn Herrington

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 15th day of December, 1964.

Leah Faye Hefke
Leah Faye Hefke, Notary Public

My commission expires June 16, 1967.