

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Bison Energy, Inc. Lic # 6581
ADDRESS 410 N. Plum
Hutchinson, KS 67501

API NO. 15-163-21,617-00-00
COUNTY Rooks
FIELD HAYDEN

**CONTACT PERSON G.J. Lett
PHONE 663-2262 (316)

PROD. FORMATION Arbuckle
LEASE NUTSCH

PURCHASER KOCH Oil
ADDRESS Box 2256, Wichita, KS. 67201


WELL NO. 1
WELL LOCATION E/2 - SE-NE

DRILLING Abercrombie Drilling, Inc.
CONTRACTOR ADDRESS 807 Union Center
Wichita, KS 67202

330 Ft. from east Line and
2145 Ft. from north Line of
the NE/4 SEC. 31 TWP. 8S RGE. 19W

PLUGGING
CONTRACTOR
ADDRESS

WELL PLAT



KCC
KGS
(Office Use)

RECEIVED
STATE CORPORATION COMMISSION
JUN - 8 1982

TOTAL DEPTH 3552 LTD. PBD
SPUD DATE 3/20/82 DATE COMPLETED 5/31/82
ELEV: GR 2045 DF KB 2050

DRILLED WITH (CABLE) (ROTARY) (STR) TOOLS

Amount of surface pipe set and cemented 208.95' DV Tool Used? 6/8/82

AFFIDAVIT

STATE OF Kansas, COUNTY OF Reno SS, I,

G.J. Lett III OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS President (FOR)(OF) Bison Energy Corp.

OPERATOR OF THE NUTSCH # 1 LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

SAID LEASE WAS COMPLETED AS OF THE 31 DAY OF May, 19 82, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIRMETH WITH NOT. CONSERVATION DIVISION Wichita, Kansas

(S) [Signature] 19 82

SUBSCRIBED AND SWORN BEFORE ME THIS 7 DAY OF May

MY COMMISSION EXPIRES: January 28, 1984

NOTARY PUBLIC

**The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; core intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOSS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand & Shale	0	218		
Shale & Sand	218	1511		
Anhydrite	1511	1542		
Shale	1542	2580		
Shale & Lime	2580	2735		
Shale	2735	3194		
Shale & Lime	3194	3277		
Lime & Shale	3277	3295		
Lime	3295	3500		
Dolomite	3500	3550		
Rotary Total Depth	3550			

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Soaks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	215.95'	Common	155	2% Gel, 3% c.c.
Production	7 7/8"	5 1/2"	14#	3550'	50-50 posmix	150	20 bbls. water 20 bbls. Mud Flush

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Soaks cement	Shots per ft.	Size & type	Depth interval
			4	SSB	3498-3506

TUBING RECORD		
Size	Setting depth	Packers set at
5 1/2"	3550	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gal. 15% mud acid inhibitor	through perforations
1000 gal. 15% demulsion acid inhibitor	" "

Rate of fluid production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
	Pumping	27.5

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	13 bbls.	none	50 MCF %	bbls. CFPS

Disposition of gas (vented, used on lease or sold)	Perforations
	3498-3506