

4-041952

1-15

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-21,207 ~~00-01~~

S2 SE NE /4 SEC. 28, 08 S, 19 W
3300 feet from S section line
660 feet from E section line

Operator license# 4335

Lease: Veverka Well # 1

Operator: Terrol Energy, Inc.

County: Rooks 111.90

Address: P.O. Box 227
Hygiene, CO 80533

Well total depth 3443 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 222 Feet
W/150 sxs cmt.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Terrol Energy, Inc. License# 4335

Address: P.O. Box 227 - Hygiene, CO 80533

Company to plug at: Hour: 9:00 A.M. Day: 15 Month: January Year 1998

Plugging proposal received from: Mike Kerns

Company: Terrol Energy, Inc. Phone: 303-772-7819

Were: 5 1/2" casing set at 3441' w/260 sxs cement. Perfs at 3441' - 3443'.

Anhy at 1470 with 625 sxs. T.O.F. at 2000' +.

Ordered 225 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls - 15 sxs gel.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [] , Part [X], None []

Completed: Hour: 12:30 P.M., Day: 15, Month: January, Year: 1998 1/22/98

Actual plugging report: R.U. Cementers to 5 1/2" casing. Squeezed 5 1/2" casing with 25 sxs 60/40 pozmix - 10% gel with 100# hulls mixed in cement, followed with 12 sxs gel, followed with 150 sxs cement with 400# hulls. Max. P.S.I. 1400#. S.I.P. 1000#. Cement at surface in 8 5/8" S.P. Job complete.

Remarks: Cemented by Allied Cement Company.

Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC , NO

Plugged through TUBING CASING X

Dakota plug: YES X, NO
Elevation: G.L.

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE 1-23-98

INV. NO. 49981

1-15