

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01407-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 28-8S-19W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: STICE Well Number: 1
County: ROOKS Total Vertical Depth: 3478 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: 125 N. MARKET STE. 1230
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3474
Surface Casing Size: 8.625 feet: 283 *#113⁰⁴*

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/31/2003 10:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8049

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 10 sxs gel spacer - 400# hulls.
Well squeezed at 2073' w/250 sxs. 1010' w/100 sxs.

Plugging Proposal Received By: BRUCE BASYE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/31/2003 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 5 1/2" - mixed and pumped 50 sxs cement with 400# hulls, followed by 10 sxs gel.
Topped with 175 sxs cement.
Max. P.S.I. 500#. S.I.P. 100#.
Hooked up to 8 5/8" - pumped 50 sxs cement.
Max. P.S.I. 400#. S.I.P. 200#.

RECEIVED
AUG 04 2003 8/4/03
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 8.5.03
INV. NO. 2004060334

JUL 31 2003

BIRD & BOREING

#1

STICE

22 28-8-19W
NW NW SE

Contr.

ROOKS

County

E. 2039 Comm.

Comp.

2-10-50 IP

50 BQFD

Tops	Depth	Datum
HEEB	3190	- 1151
LANS	3234	- 1195
ARB	3473	- 1434
T.D.	3478	- 1439

Casing

8" 283 ACID 1000
 5" 3474 10 BFPH, 50% WTR
 PMP .75 BO & 100
 BW/24 HRS

WEBSTER POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01407-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 28-8S-19W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: STICE Well Number: 1
County: ROOKS Total Vertical Depth: 3478 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: 125 N. MARKET STE. 1230
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3474 200 SX CMT
Surface Casing Size: 8.625 feet: 283 180 SX CMT

113⁰⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/28/2003 11:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MICHAEL E. NOVY Company: NOVY OIL & GAS, INC. Phone: (316) 265-4651

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel and 500# hulls.
Casing squeeze at 2073' with 250 sxs and 1010' with 100 sxs.
T.O.F. 1300'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/28/2003 1:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.U. cementers to 8 5/8" S.P. - pressured up to 500# - no cement pumped.
R.U. cementers to 5 1/2" casing - squeezed 200 sxs 60/40 pozmix - 10% gel with 300# hulls.
Casing pressured-up to Max. P.S.I. 1000#. S.I.P. 500#.

RECEIVED
JUN 05 2003
KCC WICHITA

6/5/03

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

100-

Signed Dennis Hamel
(TECHNICIAN)

INVOICED
6.5.03
2003061609

JUN 04 2003

BIRD & BOREING

#1

STICE

22 28-8-19W

NW NW SE

Contr.

ROOKS

County

E 2039

Comm.

Comp.

2-10-50 IP

50 BQD

Tops	Depth	Datum
HEFB	3190	- 1151
LANS	3234	- 1195
ARB	3473	- 1434
T.D.	3478	- 1439

Casing

8" 283 ACID 1000
 5" 3474 10 BFRH, 50% WTR
 PMP 75 BO & 100
 BW/24 HRS

WEBSTER POOL

-	+	-	+
-	+	-	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS