

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21176-00-00
Spot: N2SWSE Sec/Twnshp/Rge: 28-8S-19W
1300 feet from S Section Line, 1790 feet from E Section Line
Lease/Unit Name: STICE Well Number: 5
County: ROOKS Total Vertical Depth: 3476 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: 125 N. MARKET STE. 1230
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3457 200 SX CMT
Surface Casing Size: 8.625 feet: 167 135 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/28/2003 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MICHAEL E. NOVY Company: NOVY OIL & GAS, INC. Phone: (316) 265-4651

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel and 500# hulls.
T.O.F. 1300'. D.V. at 1455' w/375 sxs.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/28/2003 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

R.U. cementers to 8 5/8" S.P. - pressured up to 500# - no cement pumped.
R.U. cementers to 5 1/2" casing - squeezed 200 sxs 60/40 pozmix - 10% gel with 300# hulls.
Casing pressured-up to Max. P.S.I. 1000#. S.I.P. 500#.

6/20/03
RECEIVED
KANSAS CORPORATION COMMISSION
JUN 20 2003
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

6-05-03

200.3061609

Form CP-2/3

JUN 16 2003

JOHN B COLLINS
 1007 CODY 'A'
 HAYS, KS. 67601
 CONTR DREILING OIL INC CTY ROOKS #5 STICE 28-8-19W C N/2 SW SE
 GEOL LAWRENCE F. GRAY FIELD WEBSTER
 E 2027 RB 11/11/80 CARD ISSUED 2/12/81 IP OIL WELL
 2022 GL 15-163-21, 176 ARB OH 3457-3464

	+	-	+
-	+	-	+

SMP TOPS	DEPTH	DATUM
ANH	1439	+ 588
TOP	2976	- 949
HEEB	3180	-1153
TOR	3202	-1175
LANS	3218	-1191
B KC	3432	-1405
ARB	3456	-1429
TD	3460	-1433
DDTD	3464	-1437

B 5/8" 167/135sx; 5 1/2" 3457/150sx
 NO DSTS
 M/GT - CO, DD TO 3464' (ARB OH), AC
 250 GAL, POP, OIL WELL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS