

6 031573

API NUMBER 15-1950 TS-163-19160-02-04

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE NW, SEC. 32, T 8 S, R 19 W/E

3630 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Ondrasek Well # W-08

Operator: Phillips Pet. Company

County Rooks 113.45

Name & Address Rt. 3 Box 20-A

Well Total Depth 3491 feet

Great Bend, Kansas 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 125'

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated E-23,083

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: P.M. Day: 23 Month: 7 Year: 19 91

Plugging proposal received from Bill

(company name) Kelso Casing (phone) _____

were: 10 3/4 set @ 125' w/250 sx. cwc. 7" set @ 3484' w/250 sx. PBTB 3422'.

Perf. 3278' - 3418'. 7" was cemented from anhy. to surface. Order 400 sx.

65/35 poz. 10% gel. 500# hulls. Allied Cement Company. Bennie Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:00P.M. Day: 23 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT Squeezed 7" casing w/400 sx. cement blend w/500# hulls

mixed in to max. P.S.I. 150#. Close in P.S.I. 150#. Pressured up instantly on

10 3/4 annulus w/ no material taken. Cement is at surface. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
OCT 01 1991

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 10-4-91

INV. NO. 33250

Sub. S

Signed Carl Goodrow
(TECHNICIAN)