

00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163- 22,394
NW NW SW, Sec. 14, T 8 S, R 20 (W)
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Roy Well # 1

Operator: John O. Farmer
Name & P.O. BOX 352
Address Russell, Ks. 67665

County Rooks

Well Total Depth 3568 feet

115.96

Conductor Pipe: Size 0 feet

Surface Casing: Size 8⁵/₈ feet 259

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor John O. Farmer License Number 5135 Rig 220

Address same as above

Company to plug at: Hour: _____ am Day: 5 Month: June Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Herman Mick

(company name) John O. Farmer (phone) _____

were: Order 210 lbs. 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel and 8⁵/₈" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good

circulation and no fluid loss.

Signed Gilbert P. Leiker
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 8 AM Day: 5 Month: June Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 3490 w/25 sks

2nd plug @ 1580 w/25 sks

3rd plug @ 820 w/100 sks 1 sk flo-cel

4th plug @ 280 w/40 sks

5th plug @ 40 w/8⁵/₈" plug 1/2 sk hulls 10 sks

Cemented by Allied

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1984
CONSERVATION DIVISION
Wichita, Kansas

6-11-84

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 6-12-84

INV. NO. 1970

Signed Gilbert P. Leiker
(TECHNICIAN)