

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-22165-00-00

NE, Sec. 6, T 8 S, R 20 W  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5267

Lease Name Vanduvall Well # A-1

Operator: Name & Address  
K.E.E Inc.  
100 S. main  
Suite 300  
Wichita KS.

County Rooks  
Well Total Depth 3540 feet \$115.05  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 7/8 feet 246

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling License Number 5422

Address Wichita KS.

Company to plug at: Hour: AM Day: 16 Month: 10 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Wilber Drilling

(company name) Abercrombie Drilling (phone) 316 264-4301

were: order 210.5x cam. 50/50 foamix 6% Gel 390 c.c.

15x hulls 1-8 5/8 plug.

Heavy mud between all plugs

pump cam. down drill pipe

Elev. 1975 Anhydrite 1527-60 Arbuckle 3514

Dakota 1450

525: 825

Signed Dale F. Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part None

Operations Completed: Hour: 7 AM Day: 16 Month: 10 Year: 19 83

ACTUAL PLUGGING REPORT

25 5x @ 3520

25 5x @ 1540

100 5x @ 825

40 5x @ 275 15x hulls push plug to 40'

10 5x @ 40

10 5x in Rot valve

Remarks:

cementing w. Allied

I hereby certify that the above plugging instructions were given as herein stated and that I (did not) observe this plugging.

INVOICED

DATE \_\_\_\_\_  
INV. NO. 5919-W

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1983  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Dale F. Balthazor (TECHNICIAN)