

To: 6 062473
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 8-15 15-163-30326-00-01 234
SW , SEC. 6, T 8, S, R 20 WE
330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3613

Lease Name Thyfault Well # 1
County Rooks 114.23
Well Total Depth 3515' feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 205'

Operator: Hallwood Petroleum, Inc.
Name &
Address 4582 S. Ulster St. Pkwy #1700
P.O. Box 378111
Denver, Colorado 80237

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Hallwood Petroleum, Inc. License Number 3613
Address Box 404, Plainville, Kansas 67663

Company to plug at: Hour: 9:00A.M. Day: 15 Month: August Year: 19 91

Plugging proposal received from Auen Weverling
(company name) Hallwood Petroleum, Inc. (phone) 913-434-2357
were: Order 400 sk. of 60/40 posnix - 8% gel. - 5 sks. hulls.

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1991
8/23/91
CONSERVATION DIVISION
Wichita Kansas

Shot holes at 1800' & 1200' Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:50A.M. Day: 15 Month: August Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" set at 205' w/150 sks. 5 1/2" set at 3514' w/125 sks.

Top perf. at 3428'. Pumped in 2 3/8" tubing to 1800' spotted 75 sks. cement.

Pulled tubing to 900' and spotted to surface w/85 sks. cement. Hook on to 5 1/2"

casing and squeezed 140 cement w/500 P.S.I. Pumped in 8 5/8" - 100 sks. cement
w/400 P.S.I.

Remarks: By: Halliburton. Ran Line to 3300'.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (Halliburton) reserve this plugging.

Signed Gilbert G. Scheck
(TECHNICIAN) E.G.S.

DATE SEP 06 1991

INV. NO. 32970
8-15

NOV 20 1991