

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20804-00-00
Spot: CNWNENW Sec/Twnshp/Rge: 7-8S-20W
330 feet from N Section Line, 1650 feet from W Section Line
Lease/Unit Name: HAMEL Well Number: 3
County: ROOKS Total Vertical Depth: 3485 feet

Operator License No.: 3134
Op Name: G L M COMPANY
Address: PO BOX 193
RUSSELL, KS 67665

12/21

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 202 w/150 sxs cmt.
Production: Size 4.5 feet: 3301 w/100 sxs cmt.
Liner: Size feet: 113.26

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/21/2000 12:00 PM
Plug Co. License No.: 3134 Plug Co. Name: G L M COMPANY
Proposal Rcvd. from: TERRY MORRIS Company: G L M COMPANY Phone: (913) 483-2123

Proposed Plugging Method: Casing leak with fish in hole - top of tubing fish at 1100'.
Ordered 250 sxs 60/40 pozmix - 10% gel w/500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/21/2000 12:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:
R.I.H. with tubing - spotted 145 sxs cement with 400# hulls.
Cement circulated to surface. P.O.O.H. with tubing and squeezed casing with additional 55 sxs cement.
Max. P.S.I. 1000#. S.I.P. 800#.
8 5/8" S.P. - squeezed 50 sxs cement with 100# hulls.
Max. P.S.I. 200#. S.I.P. 0#.
Remarks:
Hole in top of surface pipe with fluid at surface - indicated some leakage at surface prior to plugging: Cedar Hills 1147' - 1200'.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 28 2000
12-28-2000
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY
Plugged through: TBG

District: 04

170-

Signed Dennis S. Hamel
(TECHNICIAN)

INVOICED
DATE 12/29/00
200106/21/1

DEC 26 2000

J.B. COLLINS
1007 CODY AVE.
HAYS, KS. 67601
CONTR DREILING OIL, INC.

#3 HAMEL
CTY. ROOKS

7-8-20W
NW NE NW

GEOL. ROGER WEITY
FIELD THYFAULT

K 1958 KB CM 5/11/78 CARD ISSUED 10/5/78 IP P 13 BOPD + WTR

LANS 3182-3243 OA

API 15-163-20,804

LOG TOPS	DEPTH	DATUM
ANH	1519	+ 439
B ANH	1551	+ 407
HEEB	3143	-1185
TOR	3166	-1208
LANS	3183	-1225
B KC	3385	-1427
CONG	3428	-1470
ARB	3479	-1521
RTD	3485	-1527

8-5/8" 202/150 SX, 4 1/2" 3301/100 SX
MICT - CO, PF 3239-43, 3220-24, 3182-
86, AC 3000, REC LD, POP

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS