

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-22, 096 - 00-00

TECHNICIAN'S PLUGGING REPORT

NW-NE-SW, Sec. 26, T 8 S, R 20 WE

2310 feet from N/S section line

1650 feet from W/E section line

Operator License # 5213

Lease Name WHISMAN Well # "E."-1

Operator: F. & M. OIL COMPANY  
Name &  
Address 422 UNION CENTER  
WICHITA, KANS.  
67202

County ROOFS

Well Total Depth 3625 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ABERCROMBIE DRUG. INC License Number 182

Address 801 UNION CENTER, WICHITA, KANS. 67202

Company to plug at: Hour: 12:00 PM Day: 21<sup>st</sup> Month: Oct. Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO BILL CRAIG

(company name) ABERCROMBIE DRUG. (phone) 316-262-2841

were: 8 5/8" - 247 FT SP. CUC / 185 SK CNT. COMMUD - 2% GEL - 3% CA-CL. (ALLIED)  
ORDER 200 SK 50/50 Formix 6% GEL - 3% CA-CL. AND 8 5/8" Plug  
SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.  
ARRUCKLE @ 3590 FT

Signed Marion Schmidt  
(TECHNICIAN) BOIC

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:00 PM Day: 21<sup>st</sup> Month: Oct. Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 200 SK 50/50 Formix 6% GEL 3% CA-CL. AND 8 5/8" Plug  
SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN PLUGS.  
1<sup>st</sup> Plug @ 3540 FT 1/20 SK CNT., 2<sup>nd</sup> Plug @ 1620 FT 1/20 SK CNT  
3<sup>rd</sup> Plug @ 900 FT 1/100 SK CNT., 4<sup>th</sup> Plug @ 250 FT 1/40 SK CNT.  
5<sup>th</sup> Plug <sup>SOLID BRIDGE</sup> HULLS - Plug @ 40 FT 1/10 SK CNT., 10<sup>th</sup> RAT HOLE (CIRCULATE)

Remarks: CEMENTED BY ALLIED CO.

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 31 1983

INVOICED

DATE 11-7-83  
INV. NO. 5997-W

Signed Marion Schmidt  
(TECHNICIAN) BOIC

FORM CP-2/3  
3 Rev. 9-82

10-31-83