

To: 6 062491  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-27  
API NUMBER 15- 163-23,178 -00-00 368

SE, SEC. 26, T 8 S, R 20 (W)E  
1650 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5015  
Operator: Hellar Drilling Co., Inc.  
Name & Address: 125 N. Market #1422  
Wichita, Kansas 67202

Lease Name Bouchey Well # 1  
County Rooks 118.00  
Well Total Depth 3631 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 263' w /175 sks.

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A   
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie RTD. Inc. License Number 30684  
Address Wichita, Kansas 67202

Company to plug at: Hour: 9:15A.M. Day: 27 Month: August Year: 19 91

Plugging proposal received from Harold Maley  
(company name) Hellar Drilling Co., Inc. (phone) 316-267-2745

were: Order 215 sks. 60/40 proznix - 6% gel. - 3% Cal. Cl. - 1 sk. flocele and 8 5/8" plug.  
Spot with drill pipe with no less than 36 vis. mud between all plugs, with good  
circulation and no fluid loss.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 9:15P.M. Day: 27 Month: August Year: 19 91

- ACTUAL PLUGGING REPORT
- 1st plug @ 3600' w/25 sks.
  - 2nd plug @ 1600' w/25 sks.
  - 3rd plug @ 900' w/100 sks. 1 sk. flocele.
  - 4th plug @ 300' w/40 sks.
  - 5th plug @ 40' w/10 sks.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 05 1991  
9-5-91

Remarks: 15 sks. in Rat Hole. Cement by: Allied  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I did not observe this plugging.

Signed Gilbert G. Scheck  
(TECHNICIAN) E.A.S.

DATE 9-13-91  
INV. NO. 33126  
8-27