

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 065-21, 929 00-00

TECHNICIAN'S PLUGGING REPORT

2310 feet from N (S) section line  
2310 feet from W (E) section line

Operator License # 7211

Lease Name MC DOUGAL Well # 1

Operator: L. & A. OIL COMPANY  
Name & Address: BOX 204  
BOGUE, KANSAS.  
67625

County GRAHAM

Well Total Depth 3813 feet 124.08

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 237'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BIG SPRINGS DRLLG. License Number 5381

Address MUNGER STATION BOX 8287 - WICHITA, KS. 67208

Company to plug at: Hour: 6:00 PM Day: 14 Month: FEB. Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO TERRY AUSTIN

(company name) BIG SPRINGS DRLLG. (phone) 316-681-1732

were:

8 5/8" - 237' CUC / 135' COMMON GEL - CA-CL. BY ALLIED CMT.  
ORDER 190 50/50 POZMIX GEL - CA-CL. - 1 5/8" FLANGE AND 8 5/8" PLUG

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS  
NO CIRCULATION PROBLEMS, NO SHOW OR BLOW, ELV. 2198 - ANH. 1737'  
NO ARBUCKLE

Signed Marion Schmidt  
(TECHNICIAN) 201C

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 8:30 PM Day: 14 Month: FEB. Year: 19 84

ACTUAL PLUGGING REPORT

ORDERED 190 50/50 POZMIX GEL - CA-CL. - 1 5/8" FLANGE AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS  
1<sup>ST</sup> PLUG @ 1740' / 20' CMT. - 2<sup>ND</sup> PLUG @ 960' / 100' CMT. 1 MIXED IN.  
3<sup>RD</sup> PLUG @ 270' / 50' CMT., 4<sup>TH</sup> PLUG SOLID BRIDGE @ 40' / 10' CMT.  
10" IN RAT HOLE (CIRCULATE) BY ALLIED CMT.

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
Feb 21 1984  
FEB 21 1984

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (  / did not ) observe this plugging.

Signed Marion Schmidt  
(TECHNICIAN) 201C

INVOICED  
DATE 2-23-84  
INV. NO. 0342  
2-14