

6-11

95

4- 060319

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-21,343 00-000
SW NE NW /4 SEC. 33, 08 S, 21 W
4290 feet from S section line
3630 feet from E section line

KCCZAP

Operator license# _____ Lease Slair Fountain well # 33-33

Operator: State of Kansas - Fee Fund County Graham

Address: Bob Havan Well total depth 3716 feet
District #4 Office Conductor Pipe: 0 inch @ 0 feet
Hays, Kansas 67601 Surface pipe 8 5/8 Inch @ 208 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Pipe Recovery, Inc. License# _____

Address: P.O. Box 7, Great Bend, Kansas 67530

Company to plug at: Hour: 1:00P.M. Day: 11 Month: June Year: 92

Plugging proposal received from: District Staff

Company: Kansas Corporation Commission Phone: 913-628-1200

Were: Order 300 sxs. 60/40 posmix - 8% gel. and hulls.
Clean casing out to plugging depth and spot cement
Perf. at 700'.

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1992
JUN 26 1992
CONSERVATION DIVISION
Wichita, Kansas


Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All], Part], None]

Completed: Hour: 7:15P.M., Day: 11, Month: June, Year: 92

Actual plugging report: 8 5/8" to 208'. 4 1/2" to 3703'. Bridge and
bad casing from 1150' to 1600' - plugging depth. Cleaned out sand and
junk to 1600' with tubing and bit. Pump 70 sxs. cement. Pulled tubing
and tied onto production casing and pumped 100 sxs. cement. Perf. at
689' in solid cement. Pumped 130 sxs. cement and 500# hulls. Cement
to surface in annulus - no stretch in casing at 90,000#. Cement
confirmed to 700' with charge used to perf. casing. Max. 750#.
S.I.P. 400#. 11 working Days on well

Remarks: _____
Condition of casing (in hole): GOOD _____ BAD Anhy. plug: YES _____ NO
Bottom plug (in place): YES _____, CALC _____, NO Dakota plug: YES _____, NO _____
Plugged through TUBING , CASING _____, Elevation: 2179 BL

I did / did not observe the plugging. 

APG