

6040480

API NUMBER 15-065-20444-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE-NENE, SEC. 1, T. 8 S, R. 22 W E  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9173  
Operator: H-30 Stelling Co.  
Name & Address: 251 N. Water  
S. 10  
Wichita, Ks 67202

Lease Name Buckner Well # 1  
County Grady 119.15  
Well Total Depth 3666 feet  
Conductor Pipe: Size \_\_\_\_\_ feet \_\_\_\_\_  
Surface Casing: Size 8 5/8 feet 207' w/1500x

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cont. Co. License Number \_\_\_\_\_  
Address Russell, Ks

Company to plug at: Hour: 12:15P. Day: 16 Month: 10 Year: 19 85

Plugging proposal received from Leslie Quinton  
(company name) H-30 (phone) \_\_\_\_\_

were: 5 1/2" csg set @ 3665' w/125 cont. -  
holes in csg. @ 1569' and 1150' - Perfor - K.C.  
Ordered 300 sx 6 3/4 prog 6 7/8 gel, 40 sx gel,  
+ 10 sx hulls.

Plugging Proposal Received by Dennis J. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15pM Day: 16 Month: 10 Year: 19 85

ACTUAL PLUGGING REPORT Pumped in 5 1/2" csg, -> 25 sx cont w/1 hull,  
-> 10 sx gel w/1 sx hulls, -> 25 sx cont w/1 sx hulls, ->  
10 sx gel w/1 sx hulls, -> 125 sx cont w/1 sx hulls:  
Max P.S.I. 500# - Shut-in 300# P.S.I  
8 5/8" S.P. -> pumped in 50 sx cont w/1 hulls, -> 6 sx gel  
w/hull, -> 100 sx cont w/1 hulls: MAX P.S.I 900# - Shut-in 500#

Remarks: (cont. down @ 250' below cellar - filled w/redi-mix)  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

RECEIVED  
STATE CORPORATION COMMISSION

DATE NOV 12 1985

Signed Dennis J. Hamel  
(TECHNICIAN)

NOV 4 1985  
NOV 4 1985

INV. NO. 10958

DEC 13 1985  
CONSERVATION DIVISION  
Wichita, Kansas