



15-163-20285-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

JAN 9 1970  
CONSERVATION DIVISION  
Wichita, Kansas

1-9-70

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Parks of Gabbert-Jones has this  
date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: I. O. Miller

Complete Address: 619 Brown Bldg., Wichita, Ks.

Lease Name: Balthazor Well No. 1

Location: NW NW SE Sec. 22 Twp. 8 Rge. (E)(W) 20

County: Rooks Total Depth 3580' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Parks was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 600' and displace  
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey  
Conservation Division Agent