



15-163-20285-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1978
9-17-78
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Curtis of Duke Drlg. has this

date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.Operator's full Name: National Developement Co.Complete Address: 300 W. Douglas, Suite ⁶³⁸ 365, Wichita, Ks.Lease Name: (OWWO) Balthazor ~~(XXXX)~~ Well No. 1Location: NW NW SE Sec. 22 Twp. 8 Rge. (E)(W) 20County: Rooks Total Depth 1579' Oil Well Gas Well Input Well SWD Well D & A Lost Hole XXMr. Curtis was instructed to plug the well as follows:Gun pits, circulate heavy mud, set 70 sk cmt plug at 600' thru drillpipe. Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavymud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent