



15-163-19152-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1970

CONSERVATION DIVISION
Wichita, Kansas

11-30-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gline of Messman -Rinehart has this

date requested permission to plug the following described well:

Mr. Gline guarantees payment of the plugging fee.

Operator's full Name: Messman -Rinehart Oil Co.

Complete Address: 1432 Wichita Plaza Wichita, Kansas

Lease Name: Berland Well No. 1

Location: NE NE SE Sec. 28 Twp. 8 Rge. 20 (E)(W) XX

County: Rooks Total Depth 3604' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Gline was instructed to plug the well as follows:

RTD 3604' 13" csg set at 353' cwc Gmt. Mat. 140 sk reg poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 750' and displace

70 sk cmt thru drill pipe. Heavy mud to 330' set cementing plug and

displace 50 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 20 sk cmt to base of cellar.

Very truly yours,

Leo F. Messing
Conservation Division Agent